

Exam : 650-325

Title : SP Video Phase II Cable

Access Networks

Version: Demo

- 1. Using current Ciscoproducts, how are redundantoptical links terminated at the node?
- A. It is not possibleto have redundantlinks to the node
- B. Install two nodes in random
- C. Put an optical switch in each node
- D. Install dual optical receivers in each node

Answer: D

- 2. What is the approximate attenuation of single-mode optical fiber at a wavelength of 1310nm.?
- A. 0.35 db per km
- B. 2.00 db per km
- C. 0.25 db per km
- D. 3.00 db per km

Answer: A

- 3.In an HFC network, where does 75-95% of 75-95ingressoriginate?
- A. In the RF Feeder System
- B. In theRF Distributionsystem
- C. In the optical links
- D. In the Subscribers homes

Answer: B